



# **Matamata-Piako District Plan Review**

## **Plan Change 53 – Settlements**

### **Hearing Report**

**Resource Management Act 1991, Section 42A Report**

## **Attachment B – Proposed Amendments to Notified Plan Provisions**

**May 2021**



# Proposed Amendments to Notified Plan Provisions



**PLAN CHANGE 53**  
**PROPOSED NEW SECTION 16**  
**AND PLAN PROVISIONS FOR**  
**MATAMATA-PIAKO DISTRICT PLAN**

**HEARING VERSION FORMING PART OF S.42A REPORT**

## 16 Settlement Zone

### Settlement Zone Issues

The Matamata-Piako District has a number of small rural settlements which provide for residential units, community facilities and buildings and in some cases commercial and industrial activities.

The Settlement Zone provides a bespoke zone and a set of rule mechanisms specifically designed to:

- recognise existing land use activities,
- ~~and to enable the new activities that are compatible with the character of these areas,~~  
and
- ~~and that~~ avoid or minimise the potential for reverse sensitivity effects on existing activities including major industry<sup>1</sup>.

Minimum lot size and density standards have been developed for the settlement areas based on the low-density character of these areas and also taking into account the provision of public and private three water services<sup>2</sup>.

The settlement areas are largely unserviced and therefore any new development will need to ensure that adequate provision for servicing can be accommodated on site. For those settlements with wastewater reticulation, any new development will need to be accommodated within the capacity of the existing network and treatment works as no upgrading of the Council reticulation or wastewater system is proposed.

The settlements areas accommodate a range of land use activities with residential activities being the predominant land use. The Settlement Zone and rule mechanisms recognise and provide for a ‘mixed use’ approach to existing and future development with performance standards and rules designed to reduce and mitigate any reserve sensitivity or conflict between activities.

### Settlement Zone Objectives

SETZ O1	To recognise and provide for a mix of land use activities within identified settlement areas that reflect and provide for the needs of the local communities and businesses <u>while avoiding or minimising the potential reverse sensitivity effects on existing land use activities including major industry<sup>3</sup>.</u>
SETZ O2	Residential activities are predominantly provided for in identified precinct areas.
SETZ O3	Industrial and Commercial activities are predominantly provided for in identified precinct areas and are compatible with surrounding residential activities.

<sup>1</sup> Sub Fonterra 5.1

<sup>2</sup> Sub Grayling 3.2, 3.3, and 3.4

<sup>3</sup> Sub Fonterra 5.2

SETZ O4	To promote land use activities which support the long term social and economic cohesion of settlements.
SETZ O5	To manage activities in a manner that gives certainty to the community regarding the potential location and effects of activities.
SETZ O6	Land-use, subdivision and infrastructure are planned in an integrated manner that does not compromise the supply and capacity of public and private services.

## Settlement Zone Policies

SETZ P1	To ensure compatibility between activities within the Settlement Zone by managing and controlling the scale and nature of activities.
SETZ P2	To maintain appropriate standards of amenity and design through setting performance standards for the bulk and location of buildings across all precincts.
SETZ P3	To provide for different land use activities and to mitigate reverse sensitivity and potential conflicts between activities by identifying residential, commercial and industrial precincts within the settlement areas.
SETZ P4	To ensure that any industrial activities within the industrial precincts are of a size, scale and intensity which is compatible with surrounding land use activities.
SETZ P5	To provide for the subdivision of land which complements and maintains the character and amenity of surrounding sites.
SETZ P6	Subdivision and development reliant on public <u>three waters</u> infrastructure <u>and services</u> shall not cause or lead to additional demands <u>for, or an extension of, the public network.</u> <sup>4</sup>
SETZ P7	Subdivision and development <del>that is</del> reliant on <u>private three waters</u> infrastructure and services shall be in accordance with the provisions of the regional <u>and district</u> plans, and any approved water take or discharge consents. <sup>5</sup>
SETZ P8	Where car parking is proposed or available on site, the design and construction of the access, manoeuvring and car parking areas shall ensure the safety and efficiency of all users, including pedestrians and cyclists.

## Activity Status Rules

### PREC1 - Residential Precinct

<sup>4</sup> Sub Powerco 4.3

<sup>5</sup> Sub Powerco 4.3

<p><b>Permitted Activities</b></p> <p>All permitted activities must comply with the general and relevant activity specific performance standards. The general performance standards are listed in SETZ R1(1) to SETZ R1(4). Any activity specific standards are identified in the following activity rules.</p>
<p><b>PREC1(1) One Residential Unit</b></p>
<p><b>General Performance Standards</b></p> <p>Refer Rules SETZ R1(1) to SETZ R1(4).</p> <p>Note: The provisions of the Waikato Regional Plan will need to be complied with for any on site effluent system.</p> <p><b>Activity Specific Performance Standards</b></p> <p><u>Outdoor Living Space</u></p> <p>Every residential unit (excluding minor residential unit) shall have an area of open space which shall:</p> <ul style="list-style-type: none"> <li>• Have a minimum area of 80m<sup>2</sup> and minimum width of 3m. This space may include balconies, decks having a minimum area of 10m<sup>2</sup>, with no dimension less than 1.8m and conservatories;</li> <li>• Be capable of containing a circle of 6m in diameter at some location within the area of open space, and located to the north, east or west of the unit. This area shall be at ground level and may include decks up to 1m above ground;</li> <li>• Be unobstructed by vehicle access, parking and buildings; and</li> <li>• Be directly accessible from the main living area.</li> </ul>
<p><b>PREC1(2) Minor Residential Unit</b></p>
<p><b>General Performance Standards</b></p> <p>Refer Rules SETZ R1(1) to SETZ R1(4).</p> <p><b>Activity Specific Performance Standards</b></p> <p>A <i>Minor Residential Unit</i> shall comply with the following performance standards:</p> <ol style="list-style-type: none"> <li>(i) The minimum net site area shall be 600m<sup>2</sup>;</li> <li>(ii) The maximum floor area of the unit shall be 60m<sup>2</sup>;</li> <li>(iii) An attached carport of no more than 18m<sup>2</sup> is permissible;</li> <li>(iv) The vehicle access shall be from the vehicle crossing serving the primary residential unit;</li> <li>(v) The minor residential units shall be located within 40m of the primary residential unit;</li> <li>(vi) A minimum outdoor living space of 20m<sup>2</sup> exclusive to the minor dwelling shall be provided with minimum dimension of 3m. This shall be unobstructed by vehicle access, parking, and buildings and shall be directly accessible from the main living area; and</li> <li>(vii) All on site activities must individually and collectively comply with all permitted activity performance standards.</li> </ol>

<b>PREC1(3) Home Business</b>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p> <p><b>Activity Specific Performance Standards</b> A <i>Home Business</i> shall comply with the following performance standards:</p> <ul style="list-style-type: none"> <li>(i) A maximum of two full time equivalent positions may be employed in the home business and it must include at least one permanent resident of the site;</li> <li>(ii) The home business shall not involve the parking of heavy vehicles (Gross Vehicle Weight of 3,500kg or more) on site;</li> <li>(iii) The sale of goods and/or services <u>directly to customers</u><sup>6</sup> from the site is limited to those produced on site;</li> <li>(iv) The total area dedicated to a home occupation shall be limited to 60m<sup>2</sup> floor area, This may include up to 20m<sup>2</sup> outdoor areas for the activity including storage subject to this area being screened by fencing and/or landscaping to a minimum height of 1.8m;</li> <li>(v) A maximum outdoor area of 10m<sup>2</sup> for the display of goods for sale in addition to (iv);</li> <li>(vi) Includes non-self-contained B&amp;B for up to six people;</li> <li>(vii) All on site activities must individually and collectively comply with all permitted activity performance standards;</li> <li>(viii) Any private day care activity shall be limited to four children (excluding children permanently resident); <del>and</del></li> <li>(ix) Shall not involve any pet day care or grooming services, <u>and</u></li> <li>(x) <u>The hours for delivery and collection of goods as well as onsite customer visits within the Residential Precinct shall be between: 7.30am to 5.30 pm – Monday to Friday</u><sup>7</sup></li> </ul>
<b>PREC1(4) Accessory Building</b>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p>
<b>PREC1(5) Activities and buildings on public reserves as provided by a Management Plan under the Reserves Act 1977 or by a Conservation Management Strategy under the Conservation Act 1987.</b>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p>

<sup>6</sup> Sub MPDC Staff 10.1

<sup>7</sup> Sub MPDC Staff 10.2

<b>PREC1(6) Demolition of buildings and structures except those outlined in Schedules 1, 2, and 3.</b>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p>
<b>PREC1(7) Earthworks</b>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p> <p><b>Activity Specific Performance Standards</b> Earthworks shall comply with the following performance standards:</p> <ul style="list-style-type: none"> <li>(i) Max cut or fill height -             <ul style="list-style-type: none"> <li>- 0.5m within minimum building set back</li> <li>- 1.5m outside minimum building set back.</li> </ul> </li> <li>(ii) All site works to be reinstated within 6 months of works commencing.</li> <li>(iii) Max volume of earthworks 100m<sup>3</sup> within any 12 month period.</li> <li>(iv) Works must not affect or be located within a scheduled item (Schedule 1 – 3).</li> <li>(v) Works cannot involve the excavation or disposal of contaminated land/materials.</li> <li>(vi) Works shall be set back 5m from any overland flow path and 10m from any water body.</li> </ul> <p>Exclusion: Any earthworks which;</p> <ul style="list-style-type: none"> <li>• have been approved as part of a land use or subdivision consent,</li> <li>• <u>are for the any</u> removal of topsoil for building foundations and/or driveways, <u>or</u></li> <li>• <u>any earthworks associated with utility installation, maintenance , upgrading and / or removal where the ground surface is fully reinstated within one month from when the work started</u><sup>8</sup>.</li> </ul>
<b>PREC1(8) Temporary Activities Listed in Rule 4.11.1.</b>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p>
<b>PREC1(9) Relocatable Buildings.</b>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p>

<sup>8</sup> Sub Powerco 4.4



**PREC1(10) Amateur Radio Configuration<sup>9</sup>**

**General Performance Standards**

Nil.

**Activity Specific Performance Standards**

An Amateur Radio Configuration shall comply with the following performance standards:

Amateur radio configurations shall comply with the following performance standards

- (i) there are no more than 6 antennas and aerials per site;
- (ii) no part of any aerial, antenna or mast associated with amateur radio configuration overhangs any site boundary;
- (iii) within any Residential, Commercial or Industrial Precinct which adjoins, or is opposite to, a Residential Precinct site, all support structures, aerials and antennas are located no closer than 5 m to the road boundary, or 3 m to any other affected site boundary (except that guy wires and poles up to 2m in height may be located within 1.5m of the site boundary but not the road boundary); and
- (iv) for antennas:
  - a. where attached to a building or other structure(including a mast), provided that radio and telecommunications antenna do not exceed:
    - i. for an antenna dish; 2m in diameter, or
    - ii. for panel antenna: 4m<sup>2</sup> in area; and
    - iii. a height of 4m above the point of attachment to a building and no higher than the top of any mast
  - b. provided there is no more than one pedestal mounted antenna per site, which:
    - i. is pivoted less than 4m above the ground with a maximum diameter of 5m and a maximum height of 6.5m;
    - ii. complies with the bulk and location standards for buildings in the zone in which they are located; and
    - iii. if guy wires are used, where these do not exceed 12mm in diameter; and
- (v) for aerials:
  - a. provided any element making up an aerial does not exceed 80mm in diameter;
  - b. for horizontal HF yagi aerials, provided the maximum element length does not exceed 14.9m, and maximum boom length does not exceed 13m; and
  - c. for whip aerials, provided the maximum length does not exceed 3.5m in height above the maximum height for the support structure; and
- (vi) for support structures (masts):
  - a. provided there is only one primary mast per site, which does not exceed a maximum height of 20m. This mast may be a pole of lattice mast, and may be guyed or self-supporting. Lattice masts shall be no more than:
    - i. 1000mm in outside diameter up to 9m in height
    - ii. 420mm in outside diameter above 9m in height;
  - b. provided there is only one secondary mast per site with a maximum height of 12m. This mast may be fitted with a rotator for VHF and/or UHF aerials; and
  - c. provided all masts (except for as provided for in clause (vi)(a) above) shall be less than 115mm in outside diameter.

<sup>9</sup> Sub NZART 6.1

**Advice Note: Any Amateur Radio Configuration will also need to comply with the provisions of the Building Act and New Zealand standard NZS 2772.1:1999 Radiofrequency fields – Maximum exposure levels.**

### Controlled Activities

All controlled activities must comply with the general and relevant activity specific performance standards. The general performance standards are listed in SETZ R1(1) to SETZ R1(4). The activity specific standards are identified in the following activity rules.

### PREC1(11) Two or more *Residential Units* (~~Standard Density~~)<sup>10</sup>

#### General Performance Standards

Refer Rules SETZ R1(1) to SETZ R1(4).

#### Activity Specific Performance Standards

- (i) The maximum density for residential units on a site which is served by a public reticulated wastewater supply is one residential unit per 1,000m<sup>2</sup> net site area.
- (ii) The maximum density for residential units on a site which is not served by a public reticulated wastewater supply is one residential unit per 2,500m<sup>2</sup> net site area.
- (iii) Each residential unit must comply with the subdivision standards set out in Rule 6.2 and the application shall ~~nominate~~ show<sup>11</sup> internal lot boundaries to demonstrate compliance with the relevant performance standards.

#### Assessment Criteria

General Criteria - Rule SETZ R2(1).

Specific Criteria - Rule SETZ R2(2).

#### Non-compliance with Activity Specific Performance Standards

Refer PREC1(13) (i) or (ii).

### Restricted Discretionary Activities

All restricted discretionary activities must comply with the general and relevant activity specific performance standards. The general performance standards are listed in SETZ R1(1) to SETZ R1(4). The activity specific standards are identified in the following activity rules.

<sup>10</sup> Sub Grayling 3.2, 3.3, and 3.4

<sup>11</sup> Sub MPDC Staff 10.3

<b>PREC1(12) Any permitted or controlled activity which does not comply with one or two performance standards unless otherwise stated in the performance standard rule</b>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p> <p><b>Assessment Criteria</b> General Criteria - Rule SETZ R2(1) Specific Criteria - Rule SETZ R2(3)</p>

<b>Discretionary Activities</b>
<p>All discretionary activities must comply with the general and relevant activity specific performance standards. The general performance standards are listed in SETZ R1(1) to SETZ R1(4). Any activity specific standards are identified in the following activity rules.</p> <p>The assessment criteria Rule SETZ R2(1) to SETZ R2(3) may be used to inform and guide the assessment of a discretionary activity. However, there is no limit or restriction on the matters or effects that may be assessed.</p>
<b>PREC1(13) Any permitted or controlled activity which does not comply with three or more performance standards unless otherwise stated in the performance standard rule.</b>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p>
<b>PREC1(14) Two or more <i>Residential Units (Medium-Density)</i><sup>12</sup></b>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p> <p><b>Activity Specific Performance Standards</b></p> <ul style="list-style-type: none"> <li>(i) The maximum density for residential units on a site which is served by a public reticulated wastewater supply is one residential unit per 600m<sup>2</sup> net site area.</li> <li>(ii) The maximum density for residential units on a site which is not served by a public reticulated wastewater supply is one residential unit per 1,000m<sup>2</sup> net site area.</li> <li>(iii) Each residential unit must comply with the subdivision standards set out in Rule 6.2 and the application shall <del>neminate</del> <u>show</u><sup>13</sup> internal lot boundaries to demonstrate compliance with the relevant performance standards.</li> </ul> <p><b>Assessment Criteria</b> General Criteria - Rule SETZ R2(1). Specific Criteria - Rule SETZ R2(2).</p>

<sup>12</sup> Sub Grayling 3.2, 3.3, and 3.4

<sup>13</sup> Sub MPDC Staff 10.3

<p><b>Non-compliance with Activity Specific Performance Standards</b> Any land use that does not comply with the PREC1(10) (i) or (ii), or PREC1 (13) (i) or (ii) shall be a Non-complying Activity.</p>
<p><b>PREC1(15) Educational facilities.</b></p>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p>
<p><b>PREC1(16) Community facilities</b></p>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p>
<p><b>PREC1(17) Accommodation facilities</b></p>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p>
<p><b>PREC1(18) Retailing</b></p>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p>
<p><b>PREC1(19) Medical facilities and veterinary clinics</b></p>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p>
<p><b>PREC1(20) Offices</b></p>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p>
<p><b>PREC1(21) Any activity not specifically listed within the Residential Precinct</b></p>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p>

<p><b>Non-complying Activities</b> The assessment criteria Rule SETZ R2(1) to SETZ R2(3) may be used to inform and guide the assessment of a non-complying activity. However, there is no limit or restriction on the matters or effects that may be assessed</p>
<p><b>PREC1(22) Light Industry.</b></p>
<p><b>PREC1(23) Industry.</b></p>

**PREC1(24) Any discretionary activity that does not comply with three or more performance standards.**

**PREC2 - Commercial Precinct**

**Permitted Activities**

All permitted activities must comply with the general and relevant activity specific performance standards. The general performance standards are listed in SETZ R1(1) to SETZ R1(4). Any activity specific standards are identified in the following activity rules.

Note: See specific activity rule **PREC2(17)** for Commercial Precinct - Waitoa

**PREC2(1) Permitted Activities as provided for by the following rules;**

- **PREC1(1) One Residential Unit**
- **PREC1(2) Minor Residential Unit**
- **PREC1(3) Home Business**
- **PREC1(4) Accessory Building**
- **PREC1(5) Activities on Reserves**
- **PREC1(6) Demolition of Buildings and Structures**
- **PREC1(7) Earthworks**
- **PREC1(8) Temporary Activities**
- **PREC1(9) Relocatable Buildings**
- **PREC1(10) Amateur Radio Configurations<sup>14</sup>**

**General Performance Standards**

Refer Rules SETZ R1(1) to SETZ R1(4).

Note: The provisions of the Waikato Regional Plan will need to be complied with for any on site effluent system.

**Activity Specific Performance Standards**

Refer specific performance standards as per relevant rule.

**PREC2(2) Educational facilities**

**General Performance Standards**

Refer Rules SETZ R1(1) to SETZ R1(4).

**PREC2(3) Accommodation facilities**

**General Performance Standards**

Refer Rules SETZ R1(1) to SETZ R1(4).

**PREC2(4) Retailing**

<sup>14</sup> Sub NZART 6.1

<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p>
<p><b>PREC2(5) Medical facilities and veterinary clinics</b></p>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p>
<p><b>PREC2(6) Offices</b></p>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p>

<p><b>Controlled Activities</b> All controlled activities must comply with the general and relevant activity specific performance standards. The general performance standards are listed in SETZ R1(1) to SETZ R1(4). The activity specific standards are identified in the following activity rules.</p>
<p><b>PREC2(7) Two or more Residential Units (Standard Density)</b></p>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p> <p><b>Activity Specific Performance Standards</b></p> <ul style="list-style-type: none"> <li>(i) The maximum density for residential units on a site which is served by a public reticulated wastewater supply is one residential unit per 1000m<sup>2</sup> net site area.</li> <li>(ii) The maximum density for residential units on a site which is not served by a public reticulated wastewater supply is one residential unit per 2500m<sup>2</sup> net site area.</li> <li>(iii) Each residential unit must comply with the subdivision standards set out in Rule 6.2 and the application shall nominate internal lot boundaries to demonstrate compliance with the relevant performance standards.</li> </ul> <p><b>Assessment Criteria</b> General Criteria - Rule SETZ R2(1) Specific Criteria - Rule SETZ R2(2)</p> <p><b>Non-compliance with Activity Specific Performance Standards</b> Any land use that does not comply with the R2(7) (i) or (ii), shall be a Discretionary Activity.</p>

<p><b>Restricted Discretionary Activities</b></p> <p>All restricted discretionary activities must comply with the general and relevant activity specific performance standards. The general performance standards are listed in SETZ R1(1) to SETZ R1(4). Any activity specific standards are identified in the following activity rules.</p>
<p><b>PREC2(8) Any permitted or controlled activity which does not comply with one or two performance standards unless otherwise stated in the performance standard rule</b></p>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p> <p><b>Assessment Criteria</b> General Criteria - Rule SETZ R2(1) Specific Criteria - Rule SETZ R2(3)</p>
<p><b>PREC2(9) Community facilities</b></p>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p> <p><b>Activity Specific Performance Standards</b> The hours of operation shall be limited to between 7am and 10pm.</p> <p><b>Assessment Criteria</b> General Criteria - Rule SETZ R2(1) Specific Criteria - Rule SETZ R2(3)</p>
<p><b>PREC2(10) Light industry</b></p>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p> <p><b>Activity Specific Performance Standards</b> The hours of operation shall be limited to between 7am and 10pm.</p> <p><b>Assessment Criteria</b> General Criteria - Rule SETZ R2(1) Specific Criteria - Rule SETZ R2(3)</p>

<p><b>Discretionary Activities</b></p> <p>All discretionary activities must comply with the general and relevant activity specific performance standards. The general performance standards are listed in SETZ R1(1) to SETZ R1(4). The activity specific standards are identified in the following activity rules.</p> <p>The assessment criteria Rule SETZ R2(1) to SETZ R2(3) may be used to inform and guide the assessment of a discretionary activity. However, there is no limit or restriction on the matters or effects that may be assessed.</p>
<p><b>PREC2(11) Any permitted or controlled activity which does not comply with three or more performance standards unless otherwise stated in the performance standard rule.</b></p>
<p><b>General Performance Standards</b></p> <p>Refer Rules SETZ R1(1) to SETZ R1(4).</p>
<p><b>PREC2(12) Any restricted discretionary activity which does not comply with one or more performance standards unless otherwise stated in the performance standard rule.</b></p>
<p><b>General Performance Standards</b></p> <p>Refer Rules SETZ R1(1) to SETZ R1(4).</p>
<p><b>PREC2(13) Any activity not specifically listed in the Commercial Precinct</b></p>
<p><b>General Performance Standards</b></p> <p>Refer Rules SETZ R1(1) to SETZ R1(4).</p>
<p><b>PREC2(14) Two or more Residential Units (Medium Density)</b></p>
<p><b>General Performance Standards</b></p> <p>Refer Rules SETZ R1(1) to SETZ R1(4).</p> <p><b>Activity Specific Performance Standards</b></p> <ul style="list-style-type: none"> <li>(i) The maximum density for residential units on a site which is served by a public reticulated wastewater supply is one residential unit per 600m<sup>2</sup> net site area.</li> <li>(ii) The maximum density for residential units on a site which is not served by a public reticulated wastewater supply is one residential unit per 1,000m<sup>2</sup> net site area.</li> <li>(iii) Each residential unit must comply with the subdivision standards set out in Rule 6.2 and the application shall nominate internal lot boundaries to demonstrate compliance with the relevant performance standards.</li> </ul> <p><b>Assessment Criteria</b></p> <p>General Criteria - Rule SETZ R2(1). Specific Criteria - Rule SETZ R2(2).</p> <p><b>Non-compliance with Activity Specific Performance Standards</b></p>



Any land use that does not comply with the R2(14) (i) or (ii), shall be a Non-complying Activity.

**Non-complying Activities**

The assessment criteria Rule SETZ R2(1) to SETZ R2(3) may be used to inform and guide the assessment of a non-complying activity. However, there is no limit or restriction on the matters or effects that may be assessed.

**PREC2(15) Industry.**

**PREC2(16) Any discretionary activity that does not comply with three or more performance standards.**

**PREC2(17) Residential Units, Minor Residential Units, Education facilities and Accommodation facilities within the Commercial Precinct at Waitoa.**

**PREC3 Settlement Zone (PREC3 - Industrial Precinct)**

**Permitted Activities**

All permitted activities must comply with the general and relevant activity specific performance standards. The general performance standards are listed in SETZ R1(1) to SETZ R1(4). Any activity specific standards are identified in the following activity rules.

**PREC3(1) Permitted Activities as provided for by the following rules;**

- **PREC1(4) Accessory Building**
- **PREC1(5) Activities on Reserves**
- **PREC1(6) Demolition of Buildings and Structures**
- **PREC1(7) Earthworks**
- **PREC1(8) Temporary Activities**
- **PREC1(9) Relocatable Buildings**
- **PREC1(10) Amateur Radio Configurations<sup>15</sup>**
- **PREC2(4) Retailing**
- **PREC2(5) Medical facilities and veterinary clinics**
- **PREC2(6) Offices**

**General Performance Standards**

Refer Rules SETZ R1(1) to SETZ R1(4).

Note: The provisions of the Waikato Regional Plan will need to be complied with for any on site effluent system.

**Activity Specific Performance Standards**

- (i) Refer specific performance standards as per relevant rule.

<sup>15</sup> Sub NZART 6.1

<b>PREC3(2) Light industry</b>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p>

<b>Controlled Activities</b>
<p>All controlled activities must comply with the general and relevant activity specific performance standards. The general performance standards are listed in SETZ R1(1) to SETZ R1(4). Any activity specific standards are identified in the following activity rules.</p>
<p><b>PREC3(3)</b> Note: There are no Controlled Activities in the Industrial Precinct. This rule is only included to retain formatting sequence.</p>

<b>Restricted Discretionary Activities</b>
<p>All restricted discretionary activities must comply with the general and relevant activity specific performance standards. The general performance standards are listed in SETZ R1(1) to SETZ R1(4). Any activity specific standards are identified in the following activity rules.</p>
<b>PREC3(4) Any permitted or controlled activity which does not comply with one or two performance standards unless otherwise stated in the performance standard rule</b>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p> <p><b>Assessment Criteria</b> General Criteria - Rule SETZ R2(1) Specific Criteria - Rule SETZ R2(3)</p>
<b>PREC3(5) Community facilities</b>
<p><b>General Performance Standards</b> Refer Rules SETZ R1(1) to SETZ R1(4).</p> <p><b>Activity Specific Performance Standards</b> The hours of operation shall be limited to between 7am and 10pm.</p> <p><b>Assessment Criteria</b> General Criteria - Rule SETZ R2(1) Specific Criteria - Rule SETZ R2(3)</p>

<p><b>Discretionary Activities</b></p> <p>All discretionary activities must comply with the general and relevant activity specific performance standards. The general performance standards are listed in SETZ R1(1) to SETZ R1(4). The activity specific standards are identified in the following activity rules.</p> <p>The assessment criteria Rule SETZ R2(1) to SETZ R2(3) may be used to inform and guide the assessment of a discretionary activity. However, there is no limit or restriction on the matters or effects that may be assessed.</p>
<p><b>PREC3(6) Any permitted or controlled activity which does not comply with three or more performance standards unless otherwise stated in the performance standard rule.</b></p>
<p><b>General Performance Standards</b></p> <p>Refer Rules SETZ R1(1) to SETZ R1(4).</p>
<p><b>PREC3(7) Any activity not specifically listed in the Industrial Precinct</b></p>
<p><b>General Performance Standards</b></p> <p>Refer Rules SETZ R1(1) to SETZ R1(4).</p>

<p><b>Non-complying Activities</b></p> <p>The assessment criteria Rule SETZ R2(1) to SETZ R2(3) may be used to inform and guide the assessment of a non-complying activity. However, there is no limit or restriction on the matters or effects that may be assessed.</p>
<p><b>PREC3(8) Industry.</b></p>
<p><b>PREC3(9) Any residential unit or residential activity listed in the following rules;</b></p> <ul style="list-style-type: none"> <li>• PREC1(1) One Residential Unit</li> <li>• PREC1(2) Minor Residential Unit</li> <li>• PREC1(3) Home Business</li> </ul>
<p><b>PREC3(10) Any discretionary activity that does not comply with three or more performance standards.</b></p>

**SETZ R1 Performance Standards for PREC1, PREC2, and PREC3**

<p><b>SETZ R1(1) General Rule</b></p>
<p>All activities shall be required to comply with the following performance standards. Rule SETZ R1(2) to Rule SETZ R1(4) are general performance standards for all activities including linkage rules to other sections of the District Plan.</p>
<p><b>SETZ R1(2) Building Envelope</b></p> <p>Unless otherwise stated, the following performance standards apply to all buildings in the Settlement Zone.</p>

(a) <u>Maximum height</u>	
Residential Precinct and Commercial Precinct	9m
Industrial Precinct	12m
<p>The maximum height rule does not apply to a single <i>design feature</i> or <i>building component</i>, which does not exceed the maximum permitted <i>height</i> by more than 2 metres and/or an external dimension of 2 metres in any other direction (excluding diagonal measurements)</p> <p>Refer Section 8 for rules for antenna and dishes.</p>	
(b) <u>Height relative to site boundaries</u>	
<p>No part of any <i>building</i> shall exceed a height of 2m plus the shortest horizontal distance between that part of the <i>building</i> and the nearest site boundary, provided that this shall not apply;</p>	
<p>(i) to the apex of the gable ends of a roof, being no more than 1m<sup>2</sup> in area (See Appendix 2), or</p>	
<p>(ii) a <i>design feature</i> or <i>building component</i> that does not exceed an external measurement of 2 metres in any direction (excluding diagonal measurements); and</p>	
<p>(iii) subject to no more than a total of two <i>design features</i> or <i>building components</i> (including the apex of a gable end) encroaching through the height relative to boundary plane of all boundaries.</p>	
<p>Exemption: This rule does not apply between sites which are both located within the Industrial Precinct.</p>	
(c) <u>Yards (Residential Precinct and Commercial Precinct)</u>	
Front	5m, or 10m, if the front boundary is adjacent to a road with a posted speed environment of 70 km/h or more
Side and Rear	3m
Rear Sites	3m
River protection	20m
<u>Yards (Industrial Precinct)</u>	
Front	5m
Side and Rear	5m to non-Industrial Precinct boundary
River protection	20m
Adjoining Industrial Precinct	0m

**Provided that:**

- (i) Accessory buildings may be erected on any rear and/or side yard or any rear site yard so long as;
  - the written consent of all property owners contiguous to any building is obtained and Rule SETZ R1(2)(b) is not compromised, or
  - the length of all buildings erected within 1.5m of the side boundary does not exceed 12m or 50% of the boundary whichever is the lesser, and the wall of any habitable room facing the boundary shall have no windows or doors.
- (ii) For sites located along a state highway or railway line corridor, internal noise levels for buildings shall comply with the acoustic insulation standards in Rule ~~5.2.9~~ 5.2.12<sup>16</sup>.

*Advice Notes:*

*For garages and carports encroaching a front yard, see the General Access Standards in 9.1.2(ix).*

*All structures on or adjacent to site boundaries must also comply with the provisions of the Building Act.*

(d) Fences and walls

No fences or walls or a combination of these (whether separate or joined together) shall:

- exceed 2m in height within the yard setback and / or
- exceed the maximum height and height to boundary rules in SETZR1(2) (a) and (b) above.

**SETZ R1(3) Maximum Building Coverage**

Residential Precinct and Commercial Precinct

- 35% of the net site area

**SETZ R1(4) District Plan Linkage Rules – Performance Standards**

All activities shall comply with the relevant performance standards identified in the following sections of the District Plan.

- Rule 1.2 Development Suitability
- Rule 3.5: Activities adjacent to the National Grid
- Rule 3.6 Development adjacent to sub-transmission lines
- Rule 3.7 Approach and restart sight triangles at railway level crossings
- Rule 3.8 Activities adjacent to Flood Control Assets
- Rule 3.9 Signage

<sup>16</sup> Sub Kiwirail 11.5

- Rule 5.2 Noise
- Rule 5.3 Vibration
- Rule 5.4 Lighting and Glare
- Rule 5.5 Air Emissions
- Rule 5.6 Management of Disposal of wastes
- Rule 5.7 Use and Storage of Hazardous Substances
- Rule 5.9 Infrastructure and servicing
- Section 7: Development Contributions
- Section 9: Transportation (except that rules Rule 9.1.4<sup>17</sup> regarding the minimum number of carparks shall not apply)

## **SETZ R2 Assessment Criteria for PREC1, PREC2, and PREC3**

### **SETZ R2(1) General Assessment Criteria**

The following assessment criteria shall apply to all Controlled and Restricted Discretionary activities:

- (a) The extent of non-compliance with any performance standards and the degree to which this adversely affects the amenity and character of the site and surrounding area;
- (b) The degree to which on site amenity is retained for residents and the appropriate level of separation, space and amenity between sites;
- (c) The extent to which the scale and nature of the proposal including any specific site features or design mitigates the adverse effects of the activity;
- (d) Whether the activity will adversely affect or interfere with the legitimate land use and activities on surrounding sites, including potential reverse sensitivity effects on existing activities including major industry;
- (e) Traffic, parking and access effects, including the safety and efficiency of the roading network and any effects of not providing carparking; ~~and~~
- (f) The provision of three waters servicing; and
- (g) Whether adequate capacity exists to maintain acceptable levels of service within available public reticulated three waters services<sup>18</sup>

### **SETZ R2(2) Controlled Assessment Criteria - Two or more Residential Units**

Note: These specific Controlled Assessment criteria apply in addition to all other general assessment criteria and other assessment criteria resulting from the rule mechanisms that apply to the activity

<sup>17</sup> Sub MPDC Staff 10.4

<sup>18</sup> Sub Fonterra 5.11

<p>In addition, the criteria set out in Rule SETZ R2(1), the following assessment criteria shall apply to any controlled activity for two or more <i>Residential Units</i>:</p> <p>(a) The nature and design of buildings and outdoor spaces to ensure that a high level of residential amenity is provided for residents;</p> <p>(b) The future development potential of the site; and</p> <p>(c) The scale, density and design of buildings and the degree that this maintains the residential amenity and values of other surrounding sites.</p>
<p><b>SETZ R2(3) Restricted Assessment Criteria - <i>Community facilities and Light industry</i></b></p> <p>Note: These specific Restricted Discretionary Assessment criteria apply in addition to all other general assessment criteria and other assessment criteria resulting from the rule mechanisms that apply to the activity</p>
<p>In addition to SETZ R2(1), the following assessment criteria shall apply to <i>Community facilities</i> and <i>Light Industry</i> in the Commercial Precinct:</p> <p>(a) The type and location of surrounding land use activities and whether these may be affected by the scale, nature and intensity of the proposed use.</p>
<p>Note: The assessment criteria Rule SETZ R2(1) to SETZ R2(3) may be also used to inform and guide the assessment of a discretionary activity. However, there is no limit or restriction on the matters or effects that may be assessed.</p>

### SETZ R3 OTHER PLAN PROVISIONS

<p><b>SETZ R3(1) Other Plan Provisions</b></p>
<p>Any activity within the Settlement Zone will also need to be reviewed and assessed against the following rules and sections of the District Plan</p> <ul style="list-style-type: none"> <li>• Rule 1.1 Information requirements for resource consent applications</li> <li>• Rule 1.5 Notified and non-notified consents</li> <li>• Section 5 Performance Standards</li> <li>• Section 6 Subdivision</li> <li>• Section 8 Works and network utilities</li> <li>• Section 10 Natural Environments and heritage</li> <li>• Section 11 Natural Hazards</li> <li>• Section 12 Surface of Water</li> <li>• Section 13 Other Methods</li> <li>• Section 14 Monitoring</li> <li>• Section 15 Definitions</li> </ul>

**PLAN CHANGE 53**  
**PROPOSED RURAL HOUSE SITE PROVISIONS FOR**  
**MATAMATA-PIAKO DISTRICT PLAN**



### Part 3 - Development Controls

C.2.1) Delete Rule 2.2.3.4 and renumber rule numbering

- 3.4 One dwelling per Certificate of Title for a rural lot (existing at November 1996) less than or equal to 4.2ha in area

C.2.2) Amend Rule 3.2.1 to include new rule 3.2.1(iv) for Rural House Lots,

#### 3.2.1 Building envelope

(iv) Rural House Sites

For Rural Zoned lots which contain less than 2,500m<sup>2</sup>, the following yards shall apply:

- (a) Front Yard..... 15m
- (b) Side/Rear Yards..... 10m, unless the adjacent property is 1ha or less in which case a minimum side/rear yard of 5m shall apply.
- (c) For sites located along a state highway or railway line corridor, internal noise levels for buildings shall comply with the acoustic insulation standards in Rule ~~5.2.9~~ 5.2.12<sup>19</sup>.

---

<sup>19</sup> Sub Kiwirail 11.5

**PART C.3**

**PLAN CHANGE 53  
OTHER PROPOSED CHANGES TO  
MATAMATA-PIAKO DISTRICT PLAN**

### Part 3 - Signage

C.3.1) Insert New Rules for Signage into Rule 3.9.1.

	<b>Zone</b>	<b>Type of sign permitted</b>	<b>Total site signage</b>
12	Settlement Zone (Residential Precinct)	A sign stating name, profession, occupation or trade or property name.	0.5m <sup>2</sup>
13	Settlement Zone (Industrial and Commercial Precinct)	Signs related to permitted activities established on the site for the advertisement or identification of the established permitted activities.	6m <sup>2</sup>

## Part 5 - Noise

### C.3.2) Insert New Rule 5.2.11 for Noise

#### 5.2.11 Settlement Zone

(i) Residential Precinct and Commercial Precinct

The noise level ( $L_{Aeq}$ ) as measured at any point within the boundary of an adjacent Residential Precinct and Commercial Precinct site or the notional boundary of any rural dwelling shall not exceed the following:

Monday to Saturday	7.00am to 10.00pm	50dBA
At all other times including Sundays and Public Holidays		40dBA
10.00pm to 7.00am. The $L_{AFmax}$ shall not exceed 65dBA.		

The day time levels may be exceeded for infrequent and short-term noise from normal household activities such as lawn mowing and domestic use of power tools.

(ii) Commercial Precinct

The noise level ( $L_{Aeq}$ ) as measured at any point within the boundary of an adjacent Industrial Precinct site or the notional boundary of any rural dwelling shall not exceed the following:

Monday to Saturday	7.00am to 10.00pm	55dBA
At all other times including Sundays and Public Holidays		45dBA
10.00pm to 7.00am. The $L_{AFmax}$ shall not exceed 75dBA.		

(iii) Industrial Precinct

(a) The noise level ( $L_{Aeq}$ ) as measured at any point within the boundary of an adjacent Residential Precinct and Commercial Precinct site or the notional boundary of any rural dwelling shall not exceed the following:

Monday to Saturday	7.00am to 10.00pm	55dBA
At all other times including Sundays and Public Holidays		45dBA
10.00pm to 7.00am. The $L_{AFmax}$ shall not exceed 75dBA.		

- (b) The noise level ( $L_{Aeq}$ ) as measured at any point within the boundary of an adjacent Industrial Precinct site shall not exceed 65dB

**5.2.12 Noise Insulation for Rural Dwelling Sites and the Settlement Zone**

(i) Performance Standards

- (a) New (including relocated) buildings to be used for a noise sensitive activity located:

- i. Within 40m of a railway line included in the definition of “regionally significant infrastructure”;
- ii. Within 80m of a state highway or significant district road with a posted speed limit above 70km/h; or
- iii. Within 40m of a state highway or significant district road with a posted speed limit of 70km/h or less.

Shall be designed, insulated, constructed, or screened by suitable barriers and maintained to ensure that noise received within any new bedroom, habitable space, or other space containing a noise sensitive activity, will not exceed the limits below:

Space	Internal noise limit	
	Road traffic noise	Railway noise
Inside bedrooms	40dB $L_{Aeq(24h)}$	35dBA $L_{Aeq}$ (1 hour)
Inside other habitable rooms	45dB $L_{Aeq(24h)}$	40dBA $L_{Aeq}$ (1 hour)
Inside other spaces containing a noise sensitive activity	No greater than the recommended maximum design guidelines in AS/NZS 2107-2000: Acoustics – recommended design sound level and reverberation times for building interiors	

- (b) The distances referred to above are measured from the:
  - i. Edge of a railway track;
  - ii. Edge of the nearest traffic lane of the state highway;
  - iii. Face of the closest external wall of a new building.
- (c) If windows are required to be closed to achieve the noise limits above, the building shall be designed and constructed to provide an alternative means of ventilation in accordance with Clause G4 of the New Zealand Building Code.
- (d) An acoustic design report prepared by an appropriately qualified practitioner confirming compliance with the limits

above must be submitted to Council as part of any resource or building consent application.

**Advice Note: Compliance with Clause G4 will not guarantee thermal comfort. Owners should consider the installation of additional ventilation equipment such as a heat pump.**

(ii) Permitted activities

- (a) A new (including relocated) building to be used for a noise sensitive activity that has demonstrated compliance with the performance standards in 5.2.9(i) above is a permitted activity.
- (b) A new (including relocated) building, not to be used for a noise sensitive activity is a permitted activity and is not required to demonstrate compliance with the performance standards in 5.2.9(i) above.

(iii) Restricted-discretionary activities

A new (including relocated) building, to be used for a noise sensitive activity not meeting the performance standards in 5.2.9(i) above is a restricted-discretionary activity

(iv) Matters of discretion

Council has restricted its discretion to the following matters and may impose conditions relating to these matters if consent is granted:

- (a) The effects of noise from the state highway and/or railway network on the activity to be constructed/relocated;
- (b) The reverse-sensitivity effects of the activity to be constructed/relocated on the operation of the state highway and/or rail network and the ability and suitability of mitigation measures to enable the continued and uninterrupted operation of the state highway and/or railway network;
- (c) The degree of noise attenuation achieved by the noise sensitive activity;
- (d) Technical advice provided by the railway operator (KiwiRail) and/or the NZ Transport Agency.

(v) Non-notification

Applications utilising Rule 5.2.9(iii) that do not simultaneously trigger other consent requirements, shall not be publicly notified and shall not be served on any party other than the railway operator (Kiwirail) and/or the NZ Transport Agency.

## Part 5 - Lighting and Glare

### C.3.3) Amend Rule 5.4

#### 5.4 Lighting and Glare

- (i) At no time between 7.00am and 10.00pm shall any outdoor lighting be used in a manner that causes an added illuminance in excess of 125 lux, measured horizontally or vertically at the boundary of any non-Industrial zoned or non-Industrial precinct site adjoining.
- (ii) At no time between the hours of 10.00pm and 7.00am shall any outdoor lighting be used in a manner that causes:
  - (a) An added illuminance in excess of 10 lux measured horizontally or vertically at any window of an adjoining building within a non-Industrial zone or non-Industrial precinct;
  - (b) An added illuminance in excess of 20 lux measured horizontally or vertically at any point along any non-Industrial zone boundary or non-Industrial precinct.
- (iii) Where measurement of any added illuminance cannot be made because any person refuses to turn off outdoor lighting, measurements may be made in locations of a similar nature which are not affected by such outdoor lighting.
- (iv) The outdoor lighting on any site adjoining any non-Industrial zoned or non-Industrial precinct site shall be so selected, located, aimed, adjusted and screened as to ensure that glare resulting from the lighting does not cause a significant level of discomfort to any occupants of the non-industrial site.

## **Part 5 – Infrastructure and Services**

### **Insert New Advice Note Into 5.9.1**

Advice Note: There are a number of private water supply networks within the District. These are subject to statutory requirements including water quality standards. New or additional connections to these private networks must be agreed with the private supplier. Council does not have any control over the capacity or water quality of private supply networks.



## Part 6 - Subdivision

### C.3.4) Amend Activity Table 6.1

#### 6.1 Activity Table

KEY								
P	Permitted activity				C	Controlled activity		
D	Discretionary activity				RD	Restricted Discretionary activity		
N/C	Non Complying activity				PRHB	Prohibited activity		
All activities not listed in the Activity Table are deemed to be non-complying unless otherwise provided for. See Rule 2.1.5								
Type of subdivision		Zones						
		Rural	Rural-Res	Residential	Industrial	Business	Kaitiaki (Conservation)	Settlement Zone (including precincts)
<b>1.</b>	<b>All Zones</b>							
(a)	Boundary Adjustment	C	C	C	C	C	C	<u>C</u>
(b)	Bonus Protection Lots	D	D	D	D	D	D	<u>D</u>
(c)	Works and Network Utilities.	C	C	C	C	C	C	<u>C</u>
(d)	Subdivision with one or more new vacant developable lots: <ul style="list-style-type: none"> <li>• Within a National Grid Subdivision Corridor;</li> <li>• Within 20m either side of the centreline of a sub-transmission line.</li> </ul>	RD	RD	RD	RD	RD	RD	<u>RD</u>
(e)	Subdivision with one or more new vacant developable lots adjoining: <ul style="list-style-type: none"> <li>• Any state highway, or</li> <li>• A railway line included in the definition of "regionally</li> </ul>	See 6.3.1 1	See 6.3.1 1	See 6.3.11	See 6.3.1 1	See 6.3.1 1	See 6.3.11	<u>See 6.3.11</u>

KEY								
P	Permitted activity				C	Controlled activity		
D	Discretionary activity				RD	Restricted Discretionary activity		
N/C	Non Complying activity				PRHB	Prohibited activity		
All activities not listed in the Activity Table are deemed to be non-complying unless otherwise provided for. See Rule 2.1.5								
Type of subdivision		Zones						
		Rural	Rural-Res	Residential	Industrial	Business	Kaitiaki (Conservation)	Settlement Zone (including precincts)
	significant infrastructure”							
(f)	Subdivision of Scheduled Sites				D			
<b>8.</b>	<b><u>Settlement Zone</u></b>							
(a)	<u>Subdivision</u>							See <u>6.3.12</u>

*C.3.5) Insert new Performance Standards and Activity Status Rule 6.3.12*

**6.3.12 Subdivision within the Settlement Zone**

(i) Additional Performance Standards

(a) Minimum Net Lot Size (Controlled Activity)

- i. Lots connected to public wastewater reticulation  
.....1,000m<sup>2</sup>
- ii. Lots not connected to public wastewater reticulation .....  
2,500m<sup>2</sup>

(b) Minimum Net Lot Size (Discretionary Activity)

- i. Lots connected to public wastewater reticulation .....  
600m<sup>2</sup>
- ii. Lots not connected to public wastewater reticulation .....  
1,000m<sup>2</sup>

(ii) Assessment Criteria

See section 6.4 and 6.6<sup>20</sup>.

(iii) Non-compliance

Any subdivision that does not comply with Rule 6.3.12(i) (a) or (b) shall be a Non-complying activity.

*C.3.6) Insert new Discretionary Assessment Criteria Rule 6.6.3*

**6.6.3 Settlement Zone (Discretionary Activity Subdivision)**

For subdivision which is a Discretionary Activity under Rule 6.3.12, Council shall assess and take into account:

- (i) The ability of the lots to provide for wastewater disposal and treatment;
- (ii) The nature and context of surrounding land use and built form; and
- (iii) Any input, advice or consents for wastewater disposal and treatment provided by the Waikato Regional Council.

---

<sup>20</sup> Sub MPDC Staff 10.5

## Part 8 - Works and Network Utilities

C.3.7) Amend Tables 8.1.1, 8.2.1, 8.3.1, 8.4.1, 8.5.1, 8.6.1, 8.8.1, 8.9.1 to include Settlement Zone into each Activity Table.

Activity	Zones and Precincts							
	Kaitiaki (Conservation), Identified Significant Features	Residential & Rural Residential, & Settlement Zone (Residential Precincts)	Business and Settlement Zone (Commercial Precinct)	Industrial and Settlement Zone (Industrial Precinct)	Rural	Public Reserves	Formed Roads	Unformed Roads

Add Advice Note the table

For Amateur Radio Configurations within the Settlement Zone see also Rule PREC(1)(10)<sup>21</sup>

<sup>21</sup> Sub NZART 6.1



## Part 9 - Transportation

C.3.8) *Insert new rule 9.1.2(xi) to address access and manoeuvring standards as a consequence of the minimum car parking rules being withdrawn from activities within the Settlement Zone.*

(xi) Access Standards for Settlement Zone

Parking and manoeuvring areas shall be designed to ensure that all vehicles can enter and exit in a forward direction in the following circumstances;

- For any common vehicle access serving more than one activity or lot;
- For any activity which has access directly off a significant, arterial or collector road; and
- For any activity which has access directly off a road which has a posted speed limit of more than 50 km/h.

**Schedule 4: Designations**

*C.3.9) Amend Schedule 4 table to update underlying zoning.*

Designation No	Underlying Zone	Authority	Location	Purpose	Map No	Legal Description
6	<u>Business Settlement Zone</u> ( <u>Industrial Precinct</u> )	Matamata-Piako District Council	Te Poi Road Te Poi	Water Supply	41	<b>For legal description refer Schedule 4: No changes are proposed to the legal descriptions within the table.</b>
159	<u>Rural Settlement Zone</u> ( <u>Residential Precinct</u> )	Matamata-Piako District Council	Campbell Road Waihou	Proposed Reserve	23	
12	<u>Rural Settlement Zone</u> ( <u>Commercial Precinct</u> )	Matamata-Piako District Council	Morrinsville-Tahuna Road Tahuna	Water Supply	37	
101	<u>Rural Settlement Zone</u> ( <u>Industrial Precinct</u> )	Chorus New Zealand Limited	Te Poi Road Te Poi	Telecommunications and Radio Communications Purposes	41	
102	<u>Rural Settlement Zone</u> ( <u>Commercial Precinct</u> )	Chorus New Zealand Limited	State Highway 26 Waitoa	Telecommunications and Radio Communications Purposes	24	
103	<u>Rural Settlement Zone</u> ( <u>Residential Precinct</u> )	Chorus New Zealand Limited	Walton Road walton	Telephone Exchange	39	
130	<u>Rural Settlement Zone</u> ( <u>Residential Precinct</u> )	Ministry of Education	State Highway 26 Waitoa	Primary School	24	
116	<u>Rural Settlement Zone</u> ( <u>Residential Precinct</u> )	Ministry of Education	Tahuna-Ohinewai Road Tahuna	Primary School	37	
131	<u>Rural Settlement Zone</u>	Ministry of Education	Manawaru Road, Manawaru	Primary School	38	

Proposed Changes to Settlement Provisions – S.42A Report recommendations

	<u>(Residential Precinct)</u>					
153	<u>Rural Settlement Zone (Residential Precinct)</u>	Ministry of Education	State Highway 29 Hinuera	Primary School	42	
132	<u>Rural Settlement Zone (Residential Precinct)</u>	Manawaru Playcentre	Manawaru Road, Manawaru	Play Centre	38	



## **Schedule 5 and Planning Maps: Development Concept Plan**

*Remove all reference and provisions for the Te Aroha Skin Processors Limited Development Concept Plan from the District Plan and Planning Maps.*

## Definitions

**For the purpose of Plan Change 53, the following definitions will apply only in relation to activities and provisions within Section 16 of the District Plan and any associated rule mechanisms.**

**In some instance, the definitions are those mandated for adoption by the National Planning Standards. These are identified by the annotation (NPS)**

C.3.10) *Insert the following definitions into Section 15.*

Activity	Proposed Definition
Accessory building (NPS)	For the Settlement Zone, means a detached <i>building</i> , the use of which is ancillary to the use of any <i>building</i> , <i>buildings</i> or activity that is or could be lawfully established on the same <i>site</i> , but does not include any <i>minor residential unit</i> .
Allotment (NPS)	has the same meaning as in section 218 of the RMA
<u>Amateur radio configuration</u> <sup>22</sup>	<u>For the Settlement Zone means antenna, aerials and associated support structures which are owned and operated by licensed amateur radio operators.</u>
Ancillary activity (NPS)	For the Settlement Zone, means an activity that supports and is subsidiary to a primary activity.
Building (NPS)	For the Settlement Zone, means a temporary or permanent movable or immovable physical construction that is: <ol style="list-style-type: none"> <li>a. partially or fully roofed, and</li> <li>b. is fixed or located on or in <i>land</i>, but</li> <li>c. excludes any motorised vehicle or other mode of transport that could be moved under its own power.</li> </ol>
Building component	For the Settlement Zone, means a component of a <i>building</i> that is integral to and compliments its function including, but not limited to eaves, chimneys, balustrades and solar panels.
Building coverage (NPS)	For the Settlement Zone, means the percentage of the <i>net site area</i> covered by the <i>building footprint</i> .
Building footprint (NPS)	For the Settlement Zone, means, in relation to <i>building coverage</i> , the total area of <i>buildings</i> at ground floor level together with the area of any section of any of those <i>buildings</i> that extends out beyond the ground floor level limits of the <i>building</i> and overhangs the ground.
Community facility (NPS)	For the Settlement Zone, means <i>land</i> and <i>buildings</i> used by members of the community for recreational, sporting, cultural, safety, health, welfare, or worship purposes. It includes provision for any <i>ancillary activity</i> that assists with the operation of the community facility.

<sup>22</sup> Sub NZART 6.1

Design feature	For the Settlement Zone, means a distinctive part of a <i>building</i> designed for visual effect that is not integral to the day to day functioning of that <i>building</i> .
Earthworks (NPS)	For the Settlement Zone, means the alteration or disturbance of <i>land</i> , including by moving, removing, placing, blading, cutting, contouring, filling or excavation of earth (or any matter constituting the <i>land</i> including soil, clay, sand and rock); but excludes gardening, cultivation, cultivation and disturbance of <i>land</i> for the installation of fence posts.
Education facility (NPS)	For the Settlement Zone, means <i>land</i> or <i>buildings</i> used for teaching or training by child care services, schools, or tertiary education services, including any <i>ancillary activities</i> .
Height (NPS)	For the Settlement Zone, means the vertical distance between a specified reference point and the highest part of any feature, <b>structure</b> or <b>building</b> above that point.
Height in relation to boundary (NPS)	For the Settlement Zone, means the <i>height</i> of a <i>structure, building</i> or feature, relative to its distance from either the boundary of; a. a <i>site</i> ; or b. another specified reference point.
Home business (NPS)	For the Settlement Zone, means a <i>commercial activity</i> that is: a. undertaken or operated by at least one resident of the <i>site</i> ; and b. incidental to the use of the <i>site</i> for a <i>residential activity</i> .
Industrial Activity (NPS)	For the Settlement Zone, means an activity that manufactures, fabricates, processes, packages, distributes, repairs, stores, or disposes of materials (including raw, processed, or partly processed materials) or goods. It includes any <i>ancillary activity</i> to the industrial activity.
Land (NPS)	has the same meaning as in section 2 of the RMA
Light industry	For the Settlement Zone, means an industrial activity with the exception that the following activities are not defined as Light Industry; <ul style="list-style-type: none"> <li>• any activity that requires air discharge consent,</li> <li>• any activity that requires a trade waste permit,</li> <li>• depots (which cater for heavy vehicles over 3,500kg) or</li> <li>• activities that involve the maintenance or repair of vehicles or other engineering activities in outdoor areas.</li> </ul>
L <sub>Aeq</sub> (NPS)	For the Settlement Zone, it has the same meaning as 'time-average A-weighted sound pressure level' in New Zealand Standard 6801:2008 Acoustics -Measurement of Environmental Sound.
L <sub>AF(max)</sub> (NPS)	For the Settlement Zone, it has the same meaning as the 'maximum A-frequency weighted, F-time weighted sound pressure level' in New Zealand Standard 6801:2008 Acoustics – Measurement Of Environmental Sound

<p>Minor residential unit (NPS)</p>	<p>For the Settlement Zone, means a self-contained <i>residential unit</i> that is ancillary to the principal <i>residential unit</i>, and is held in common ownership with the principal <i>residential unit</i> on the same <i>site</i>.</p>
<p>Net site area (NPS)</p>	<p>For the Settlement Zone, means the total area of the <i>site</i>, but excludes:</p> <ul style="list-style-type: none"> <li>a. any part of the <i>site</i> that provides legal access to another <i>site</i>;</li> <li>b. any part of a rear <i>site</i> that provides legal access to that <i>site</i>;</li> <li>c. any part of the <i>site</i> subject to a designation that may be taken or acquired under the Public Works Act 1981.</li> </ul>
<p>Outdoor Living Space (NPS)</p>	<p>For the Settlement Zone, means an area of open space for the use of the occupants of the <i>residential unit</i> or units to which the space is allocated.</p>
<p>Residential Activity (NPS)</p>	<p>For the Settlement Zone, means the use of <i>land</i> and <i>building(s)</i> for people’s living accommodation.</p>
<p>Residential Unit (NPS)</p>	<p>For the Settlement Zone, means a <i>building(s)</i> or part of a <i>building</i> that is used for a <i>residential activity</i> exclusively by one household, and must include sleeping, cooking, bathing and toilet facilities.</p>
<p>Site (NPS)</p>	<p>For the Settlement Zone, means:</p> <ul style="list-style-type: none"> <li>a. an area of <i>land</i> comprised in a single record of title under the Land Transfer Act 2017; or</li> <li>b. an area of <i>land</i> which comprises two or more adjoining legally defined <i>allotments</i> in such a way that the <i>allotments</i> cannot be dealt with separately without the prior consent of the council; or</li> <li>c. the <i>land</i> comprised in a single <i>allotment</i> or balance area on an approved survey plan of <i>subdivision</i> for which a separate record of title under the Land Transfer Act 2017 could be issued without further consent of the Council; or</li> <li>d. despite paragraphs (a) to (c), in the case of <i>land</i> subdivided under the Unit Titles Act 1972 or the Unit Titles Act 2010 or a cross lease system, is the whole of the <b>land</b> subject to the unit development or cross lease.</li> </ul>
<p>Specified reference point</p>	<p>For the Settlement Zone, means the finished ground level as identified and approved as part of an approved subdivision consent for which S.224(c) has been granted, <u>or</u> the natural ground level, immediately below the building or building component which is being measured</p>

## Reserve Annotations


- C.3.11) *Delete annotations and descriptions of Council reserves on planning maps within the new Settlement Zone areas. Note: this does not affect designated sites.*

# Proposed Maps




	Waahi Tapu Site		DCP Area
	Protected Tree Site		Flood Hazard
	Outstanding or Significant Natural Feature		Parcel Boundary
	Heritage Site		Industrial Zone
	Designated Site		Rural Zone
	Gas Pipeline		Water Course
	Transmission Line		Kaitiaki Zone
	Gas Pipe Corridor		Road
	Noise Emission Control Boundary		Designation
	Gas Station Site		Settlement Zone - Residential Precinct
	TP Sub Trans OH Line Corridor		Settlement Zone - Commercial Precinct
	TP Sub Trans UG Cable Corridor		Settlement Zone - Industrial Precinct

# PC53 SETTLEMENTS LEGEND



This data is provided as at November 2020 [pursuant to the Local Government Official Information and Meetings Act 1987]. While every effort has been made to ensure accuracy of the data, MPDC cannot guarantee its accuracy or suitability for any specific purpose. MPDC is not responsible for the misuse or misinterpretation of the data supplied. Under no circumstances shall MPDC be liable for any actions taken or omissions made from reliance on any information contained herein from whatever source nor shall the MPDC be liable for any other consequences from any such reliance. Copyright © 2020 Matamata-Piako District Council. Cadastral information derived from Land Information NZ Crown copyright reserved.




Scale (when printed on A4)  
**1:5,000**

Date: 04/11/2020  
 Authored: A Naea (MPDC)  
 Projection: NZTM 2000








This data is provided as at November 2020 [pursuant to the Local Government Official Information and Meetings Act 1987]. While every effort has been made to ensure accuracy of the data, MPDC cannot guarantee its accuracy or suitability for any specific purpose. MPDC is not responsible for the misuse or misinterpretation of the data supplied. Under no circumstances shall MPDC be liable for any actions taken or omissions made from reliance on any information contained herein from whatever source nor shall the MPDC be liable for any other consequences from any such reliance. Copyright © 2020 Matamata-Piako District Council. Cadastral information derived from Land Information NZ Crown copyright reserved.


**Manawaru**  
District Plan - Settlement Zone and Precincts



Scale (when printed on A4)  
**1:3,000**


Date: 04/11/2020  
 Authored: A Naea (MPDC)  
 Projection: NZTM 2000






This data is provided as at November 2020 [pursuant to the Local Government Official Information and Meetings Act 1987]. While every effort has been made to ensure accuracy of the data, MPDC cannot guarantee its accuracy or suitability for any specific purpose. MPDC is not responsible for the misuse or misinterpretation of the data supplied. Under no circumstances shall MPDC be liable for any actions taken or omissions made from reliance on any information contained herein from whatever source nor shall the MPDC be liable for any other consequences from any such reliance. Copyright © 2020 Matamata-Piako District Council. Cadastral information derived from Land Information NZ Crown copyright reserved.


### Mangateparu District Plan - Settlement Zone and Precincts



Scale (when printed on A4)  
**1:4,000**


Date: 04/11/2020  
 Authored: A Naea (MPDC)  
 Projection: NZTM 2000





This data is provided as at November 2020 [pursuant to the Local Government Official Information and Meetings Act 1987]. While every effort has been made to ensure accuracy of the data, MPDC cannot guarantee its accuracy or suitability for any specific purpose. MPDC is not responsible for the misuse or misinterpretation of the data supplied. Under no circumstances shall MPDC be liable for any actions taken or omissions made from reliance on any information contained herein from whatever source nor shall the MPDC be liable for any other consequences from any such reliance. Copyright © 2020 Matamata-Piako District Council. Cadastral information derived from Land Information NZ Crown copyright reserved.


**Motumaho**  
District Plan - Settlement Zone and Precincts




Scale (when printed on A4)  
**1:2,500**

Date: 04/11/2020  
 Authored: A Naea (MPDC)  
 Projection: NZTM 2000






This data is provided as at November 2020 [pursuant to the Local Government Official Information and Meetings Act 1987]. While every effort has been made to ensure accuracy of the data, MPDC cannot guarantee its accuracy or suitability for any specific purpose. MPDC is not responsible for the misuse or misinterpretation of the data supplied. Under no circumstances shall MPDC be liable for any actions taken or omissions made from reliance on any information contained herein from whatever source nor shall the MPDC be liable for any other consequences from any such reliance. Copyright © 2020 Matamata-Piako District Council. Cadastral information derived from Land Information NZ Crown copyright reserved.




Scale (when printed on A4)  
**1:4,000**

Date: 04/11/2020  
 Authored: A Naea (MPDC)  
 Projection: NZTM 2000




This data is provided as at November 2020 [pursuant to the Local Government Official Information and Meetings Act 1987]. While every effort has been made to ensure accuracy of the data, MPDC cannot guarantee its accuracy or suitability for any specific purpose. MPDC is not responsible for the misuse or misinterpretation of the data supplied. Under no circumstances shall MPDC be liable for any actions taken or omissions made from reliance on any information contained herein from whatever source nor shall the MPDC be liable for any other consequences from any such reliance. Copyright © 2020 Matamata-Piako District Council. Cadastral information derived from Land Information NZ Crown copyright reserved.


**Te Aroha West**  
District Plan - Settlement Zone and Precincts




Scale (when printed on A4)  
**1:3,800**

Date: 04/11/2020  
 Authored: A Naea (MPDC)  
 Projection: NZTM 2000






This data is provided as at November 2020 [pursuant to the Local Government Official Information and Meetings Act 1987]. While every effort has been made to ensure accuracy of the data, MPDC cannot guarantee its accuracy or suitability for any specific purpose. MPDC is not responsible for the misuse or misinterpretation of the data supplied. Under no circumstances shall MPDC be liable for any actions taken or omissions made from reliance on any information contained herein from whatever source nor shall the MPDC be liable for any other consequences from any such reliance. Copyright © 2020 Matamata-Piako District Council. Cadastral information derived from Land Information NZ Crown copyright reserved.




Scale (when printed on A4)  
**1:8,000**

Date: 04/11/2020  
 Authored: A Naea (MPDC)  
 Projection: NZTM 2000






This data is provided as at November 2020 [pursuant to the Local Government Official Information and Meetings Act 1987]. While every effort has been made to ensure accuracy of the data, MPDC cannot guarantee its accuracy or suitability for any specific purpose. MPDC is not responsible for the misuse or misinterpretation of the data supplied. Under no circumstances shall MPDC be liable for any actions taken or omissions made from reliance on any information contained herein from whatever source nor shall the MPDC be liable for any other consequences from any such reliance. Copyright © 2020 Matamata-Piako District Council. Cadastral information derived from Land Information NZ Crown copyright reserved.




Scale (when printed on A4)  
**1:5,500**

Date: 04/11/2020  
 Authored: A Naea (MPDC)  
 Projection: NZTM 2000





This data is provided as at November 2020 [pursuant to the Local Government Official Information and Meetings Act 1987]. While every effort has been made to ensure accuracy of the data, MPDC cannot guarantee its accuracy or suitability for any specific purpose. MPDC is not responsible for the misuse or misinterpretation of the data supplied. Under no circumstances shall MPDC be liable for any actions taken or omissions made from reliance on any information contained herein from whatever source nor shall the MPDC be liable for any other consequences from any such reliance. Copyright © 2020 Matamata-Piako District Council. Cadastral information derived from Land Information NZ Crown copyright reserved.




Scale (when printed on A4)  
**1:7,500**


Date: 04/11/2020  
 Authored: A Naea (MPDC)  
 Projection: NZTM 2000







This data is provided as at November 2020 [pursuant to the Local Government Official Information and Meetings Act 1987]. While every effort has been made to ensure accuracy of the data, MPDC cannot guarantee its accuracy or suitability for any specific purpose. MPDC is not responsible for the misuse or misinterpretation of the data supplied. Under no circumstances shall MPDC be liable for any actions taken or omissions made from reliance on any information contained herein from whatever source nor shall the MPDC be liable for any other consequences from any such reliance. Copyright © 2020 Matamata-Piako District Council. Cadastral information derived from Land Information NZ Crown copyright reserved.



Scale (when printed on A4)  
**1:4,500**

Date: 04/11/2020  
 Authored: A Naea (MPDC)  
 Projection: NZTM 2000

